



Republic of the Philippines  
**BENGUET STATE UNIVERSITY**  
La Trinidad, Benguet, Philippines 2601  
Telephone No. (074) 422-2402  
Web Address: [www.bsu.edu.ph](http://www.bsu.edu.ph)

**BILL OF QUANTITIES**

PROJECT TITLE:	CONSTRUCTION OF BIODIVERSITY RESEARCH CENTER BOKOD CAMPUS PHASE II		
PROJECT LOCATION :	BSU BOKOD CAMPUS, DACLAN, BOKOD, BENGUET		
TOTAL PROJECT COST (ABC) :	PHP	4,860,000.00	
PROJECT DURATION:	85 C.D.	INCLUSIVE OF:	14 UNWORKABLE DAYS
IMPLEMENTATION MODE:	BY CONTRACT		

PROJECT DESCRIPTION	EQUIPMENT NEEDED		TECHNICAL PERSONEL	
	NO.	DESCRIPTION	NO.	DESCRIPTION
The project is a continuation of 350 square meters floor area Biodiversity Research Center Phase II.			1	Site Engineer/ Site Architect
	1	Elf Truck	1	Materials Engineer
	1	Bagger Mixer	1	Construction Foreman
	1	Bar Bender	1	Safety Officer (Part Time)
	1	Bar Cutter		
	1	Welding Machine		

ITEM NO.	DESCRIPTION	% WEIGHT	QUANTITY	UNIT	UNIT COST	TOTAL COST
I.	GENERAL REQUIREMENTS and SITE WORKS					
a.	Mobilization/Demobilization		1.00	LOT		
b.	Project Billboard		1.00	LOT		
c.	Occupational Safety and Health Program		1.00	LOT		
II.	EARTHWORKS					
a.	Gravelling of Pavement near Basketball Court , Front and Left side elevation of Building		32.81	CU.M.		
III.	PLAIN and REINFORCED CONCRETE WORKS					
a.	Reinforced Concrete (Additional Exterior Stairs), 3000 psi @ 28days		1.26	CU.M.		
b.	Formworks & False Works		1.26	CU.M.		
IV.	MASONRY WORKS					
a.	CHB Laying		119.37	SQ.M.		
b.	Plastering		136.65	SQ.M.		
V.	ELECTRICAL WORKS					
a.	Conduits and Boxes (Second Floor)		368.30	L.M.		
b.	Wires and Wiring Devices (Second Floor)		285.00	L.M.		
c.	Electrical Fixtures(Second Floor)		52.00	UNIT		
d.	Panel Board/ Boxes/ Breakers (Second Floor)		1.00	UNIT		
VI.	PLUMBING WORKS					
a.	Pipe Lines(Second Floor)		151.00	L.M.		
b.	Plumbing Fixtures ( Second Floor Only)		31.00	UNIT		
VII.	ARCHITECTURAL FINISHINGS					
a.	Ceiling Works ( Second Floor Interior)		362.96	SQ.M.		
b.	Dry wall partition		50.22	SQ.M.		
c.	Tileworks (Unglazed Floor Tiles )		385.34	SQ.M.		
d.	Tileworks (glazed wall tiles)		119.75	SQ.M.		
e.	Granite works		5.25	SQ.M.		
f.	Aluminum Windows & Partitions		20.80	SQ.M.		
g.	Doors		9.00	SETS		
h.	Painting (Second Floor Interior & Exterior walls )		1,365.81	SQ.M.		

ITEM NO.	DESCRIPTION	% WEIGHT	QUANTITY	UNIT	UNIT COST	TOTAL COST
i	Handrails and Railings (Ground Balcony and Concrete Exterior stairs)		261.43	L.M.		
VIII.	SPECIALTIES					
a.	Modular Partition (Second Floor Comfort Rooms)		31.00	SQ.M.		
b.	Ductless Benchtop Laboratory Fumehood		3.00	UNIT		
c.	Hydraulic PWD Lift		1.00	UNIT		
IX.	FIRE SAFETY (Second Floor)		24.00	UNIT		
TOTAL PROJECT COST						
BREAKDOWN OF BID COST						TOTAL COST
A.	DIRECT COST					
	EQUIPMENT LABOR MATERIALS					
B.	INDIRECT COST					
	OCM CONTRACTOR'S PROFIT TAXES					
C.	PROJECT COST(TOTAL A+B)					
TOTAL BID COST (in figures)						
Total Bid Amount in Words :						
I hereby submit the foregoing bid; and that I understood the terms and conditions of the contract						
<div>(Signature Over Printed Name of Contractor/ Bidder)</div> <div><div></div><div>POSITION</div><div></div></div> <div><div></div><div>(Name of Firm)</div><div></div></div> <div>Date</div>						