



PROJECT TITLE:	CONSTRUCTION OF BENGUET AGRI-PINOY TRADING CENTER TRUCK PARKING AREA AND CANAL LINING		
LOCATION :	Strawberry Fields, Km. 6, La Trinidad, Benguet		
TOTAL PROJECT COST :	PHP	730,000.00	
PROJECT DURATION:		20 C.D.	INCLUSIVE OF: 1 UNWORKABLE DAYS
IMPLEMENTATION MODE:	BY CONTRACT		

PROJECT DESCRIPTION	EQUIPMENT NEEDED		TECHNICAL PERSONEL	
	NO.	DESCRIPTION	NO.	DESCRIPTION
The project is the construction of a gravel concrete parking area with an area of 1,164.4 square meters. It consist of excavation works, compaction, gravel overlay, and concreting of lined canal.	1	Truck Mounted Crane	1	Site Engineer
	1	Cargo Truck (2-5T)	1	Safety Officer / Practicioner (Part Time)
	1	Water Truck	1	Construction Foreman
	1	Dumptruck		
	1	Vibratory Roller (10MT)		
	1	Motorized Road Grader, G710A		
	1	One Bagger Mixer		
	1	Bar Cutter and Bar Bender		
	1	Concrete Vibrator		

BILL OF QUANTITIES

ITEM NO.	DESCRIPTION	% WEIGHT	QUANTITY	UNIT	UNIT COST	TOTAL COST
B.5	PROJECT BILLBOARD		1.00	EACH		
B.9	MOBILIZATION, TEMPORARY STRUCTURE, UTILITIES AND SERVICES		1.00	LUMP SUM		
B.7 (2)	OCCUPATIONAL SAFETY AND HEALTH		1.00	LUMP SUM		
101(1)	REMOVAL OF ACTUAL STRUCTURES/OBSTRUCTION		2.00	LUMP SUM		
100(2)	CLEARING AND GRUBBING		1,448.40	SQ.M.		
102(2)	SURPLUS COMMON EXCAVATION		201.44	CU.M.		
105(1)a	SUBGRADE PREPARATION		1,164.40	SQ.M.		
300(2)	CRUSHED AGGREGATE SURFACE COURSE, 0.15M THK.		174.66	CU.M.		
500(3)b1	LINED CANAL		51.00	L.M.		
TOTAL BID COST						

BREAKDOWN OF BID COST					TOTAL COST
A.	DIRECT COST				
	EQUIPMENT				
	LABOR				
	MATERIALS				
B.	INDIRECT COST				
	OCM				
	CONTRACTOR'S PROFIT				
	TAXES				
C.	PROJECT COST(TOTAL A+B)				

Total bid Cost in Figures

Total Bid Cost in Words:

I hereby submit the foregoing bid, and that I understood the terms and conditions of the contract.

(Signature)
Name of Bidder/ Contractor
 Position
Name of Construction Firm/ company
 Date : _____