



Republic of the Philippines

(NAME OF CONSTRUCTION FIRM/ COMPANY)

(ADDRESS OF CONSTRUCTION FIRM/ COMPANY)

BILL OF QUANTITIES

PROJECT TITLE:	REPAIR AND IMPROVEMENT OF DIFFUSED LIGHT YAM STORAGE		
LOCATION :	BSU LA TRINIDAD COMPOUND, KM.6, BETAG, LA TRINIDAD, BENGUET		
ABC :	PHP	850,000.00	
PROJECT DURATION:	45 C.D.	INCLUSIVE OF:	7 UNWORKABLE DAYS
IMPLEMENTATION MODE:	BY CONTRACT		

PROJECT DESCRIPTION	EQUIPMENT NEEDED		TECHNICAL PERSONEL	
	NO.	DESCRIPTION	NO.	DESCRIPTION
The proposed project is a construction of a 66 sq.m. diffused light yam storage.	1	Plate Compactor (5HP)	1	Site Engineer
	1	One Bagger Mixer	1	Safety Officer
	1	Concrete Vibrator	1	Construction Foreman
	1	Bar Cutter		
	1	Bar Bender		
	1	Welding Machine		

ITEM NO.	DESCRIPTION	% WEIGHT	QUANTITY	UNIT	UNIT COST	TOTAL COST
B.5	PROJECT BILLBOARD / SIGNBOARD		1.00	EACH		
B.7	OCCUPATIONAL SAFETY AND HEALTH PROGRAM		1.50	MONTH		
B.9	MOBILIZATION / DEMOBILIZATION		1.00	LUMP SUM		
803(1)a	STRUCTURE EXCAVATION (COMMON SOIL)		13.41	CU.M.		
804(1)a	EMBANKMENT (BACKFILL FROM STRUCTURE EXCAVATION)		14.08	CU.M.		
804(4)	GRAVEL BEDDING OF FOOTING AND SOF		2.40	CU.M.		
900(7)	REINFORCED CONCRETE		12.00	CU.M.		
1046(2)a1	CHB NON LOAD BEARING, 100mm (INCLUDING REINFORCING STEEL)		17.77	SQ.M.		
1027(1)	CEMENT PLASTER FINISH		58.27	SQ.M.		
1021	CEMENT FLOOR FINISH		37.45	SQ.M.		
SPL.1	ROOFING WORKS		1.00	LUMP SUM		
1003	CARPENTRY AND JOINERY WORKS		156.00	SQ.M.		
SPL.2	YAM SEED RACK		1.00	LUMPSUM		
1011 (1)b	ALUMINUM ROLL-UP DOOR		1.00	SET		
SPL.3	ELECTRICAL WORKS		1.00	LUMPSUM		
1200	AIR CONDITIONING AND VENTILATING SYSTEM		1.00	SET		
TOTAL BID COST						

BREAKDOWN OF BID COST					TOTAL COST
A.	DIRECT COST				
	EQUIPMENT				
	LABOR				
	MATERIALS				
B.	INDIRECT COST				
	OCM				
	CONTRACTOR'S PROFIT				
	TAXES				
C.	PROJECT COST(TOTAL A+B)				

TOTAL BID COST IN FIGURES:

TOTAL BID AMOUNT IN WORDS:

I hereby submit the foregoing bid; and that I understood the terms and conditions of the contract.

(Signature)

NAME OF BIDDER/CONTRACTOR

POSITION

NAME OF CONSTRUCTION FIRM/ COMPANY

DATE: _____